HVAC Preventive Maintenance Policy

Minimum standards for planned maintenance of chillers, AHUs, cooling towers and controls

Policy statement: all HVAC plant at ICR member sites shall be maintained to a written preventive maintenance (PPM) schedule that follows the manufacturer's instructions, statutory requirements and the risk rating of the asset. Work shall be recorded in the CMMS and reviewed monthly.

1. Scope and responsibilities

- Applies to chillers, heat pumps, VRF and DX units, AHUs, FCUs, pumps, cooling towers, controls and ductwork
- The Facilities Manager owns this policy; the maintenance contractor delivers the schedule
- The Engineer in Charge approves deferrals; any deferral beyond 14 days is escalated to the Head of Facilities

2. Minimum frequencies

Asset	Task	Frequency
Chiller (water cooled)	Log readings, check oil, approach and condenser tube condition	Daily / quarterly
Chiller	Eddy-current tube test, refrigerant and oil analysis	Annually
AHU	Filter inspection, belt tension, coil cleaning	Monthly / quarterly
Cooling tower	Basin clean, fill inspection, water treatment dosing check	Monthly
Pumps	Vibration, seal and alignment check	Quarterly
Controls	Sensor calibration, valve stroke, setpoint audit	Six-monthly

3. Water quality and Legionella

Cooling tower water shall be treated and tested monthly for total bacterial count, conductivity and Legionella risk indicators. Results outside limits trigger shock dosing, a retest within 48 hours and a notification to the Head of Facilities.

4. Records and reporting

- Every task has a work order with start, finish, technician, parts and readings
- Planned compliance is reported monthly; the target is 95% on-time completion
- Repeat failures (the same fault twice in 90 days) require a documented root cause

5. Review

This policy is reviewed annually and after any plant failure that affects occupancy for more than four hours.